



ESTIMATE

Tidewater Home Improvement LLC

Class B Contractor #2705172863

414 Worster Ave

Hampton, Virginia 23669

United States

(757) 551-6413

tidehomepro.com

BILL TO

Daniel Speller

Daniel Speller

321 Janes Way

Chesapeake 23320

United States

dspell9@gmail.com

Estimate Number: 1404

Estimate Date: September 18, 2026

Valid Until: September 25, 2026

Grand Total (USD): \$2,715.74

Downspout Discharge - Buried

163

Six 3 in. x 4 in. downspout extensions all tied into ONE single buried corrugated (flexible) discharge line, 163 linear ft total, run away from the foundation and under the sidewalk toward the street to one discharge point at a pop-up emitter clear of the house.

Downspout Extension

6

Collect one 3 in. x 4 in. downspout and tie it into the buried discharge line. The downspout is cut to length at the wall and a 3x4 shoe/adaptor fitted to the 4 in. buried pipe, the pipe is run out from the foundation on grade to the connection point, and the trench is backfilled and the ground restored. Includes the 3x4 adaptor and fittings, the tie-in to the main run and one extension per downspout. Run length is measured in linear feet from the downspout to the discharge point and is priced with the buried line. - included in the buried discharge line, no separate charge.

Pop-Up Emitter

1

Discharge pop-up emitter at the end of a buried run. The emitter body is set on a bed of #57 gravel clear of the foundation and connected to the discharge line, and the ground is graded so the lid sits just at the surface. When it rains the lid pops open and releases the roof water away from the house; between storms it stays closed and keeps surface water, dirt and mulch out of the line. Includes the emitter, the connection, the gravel bed and grading. - included in the buried discharge line, no separate charge.

Sidewalk Crossing

1

Trench the buried discharge line under the sidewalk to reach the street. The walk is hand dug underneath - no concrete cutting - the line is laid on grade and backfilled, and the walk and the ground either side are left clean and level. Includes the excavation under the walk, the backfill and the surface restoration.

Miscellaneous

1

Miscellaneous - additional allowance on the drainage scope.

10% Customer Discount

-1

10% Customer Discount

5% Repeat Customer Discount

-1

5% Repeat Customer Discount



Grand Total (USD):	\$2,715.74
---------------------------	-------------------

Notes / Terms

SCOPE OF WORK

Downspout Discharge - Buried: Six 3 in. x 4 in. downspout extensions all tied into ONE single buried corrugated (flexible) discharge line, 163 linear ft total, run away from the foundation and under the sidewalk toward the street to one discharge point at a pop-up emitter clear of the house.

Downspout Extension: Collect one 3 in. x 4 in. downspout and tie it into the buried discharge line. The downspout is cut to length at the wall and a 3x4 shoe/adaptor fitted to the 4 in. buried pipe, the pipe is run out from the foundation on grade to the connection point, and the trench is backfilled and the ground restored. Includes the 3x4 adapter and fittings, the tie-in to the main run and one extension per downspout. Run length is measured in linear feet from the downspout to the discharge point and is priced with the buried line. - included in the buried discharge line, no separate charge.

Pop-Up Emitter: Discharge pop-up emitter at the end of a buried run. The emitter body is set on a bed of #57 gravel clear of the foundation and connected to the discharge line, and the ground is graded so the lid sits just at the surface. When it rains the lid pops open and releases the roof water away from the house; between storms it stays closed and keeps surface water, dirt and mulch out of the line. Includes the emitter, the connection, the gravel bed and grading. - included in the buried discharge line, no separate charge.

Sidewalk Crossing: Trench the buried discharge line under the sidewalk to reach the street. The walk is hand dug underneath - no concrete cutting - the line is laid on grade and backfilled, and the walk and the ground either side are left clean and level. Includes the excavation under the walk, the backfill and the surface restoration.

Miscellaneous: Miscellaneous - additional allowance on the drainage scope.

10% Customer Discount: 10% Customer Discount

5% Repeat Customer Discount: 5% Repeat Customer Discount

JOB DESCRIPTION

Roof water from the six downspouts currently discharges against the house, washing out dirt and mulch and leaving water at the foundation. This estimate ties all six downspouts into one single buried corrugated (flexible) pipe discharge line, runs it under the sidewalk to the street, and discharges at one pop-up emitter clear of the house.

NOT INCLUDED: gutter cleaning or gutter repair; replacement of the existing gutters and downspouts; landscaping, sod or mulch restoration; irrigation and invisible fence lines; interior work.

Discounts: the totals below include a 10% customer discount and a 5% repeat-customer discount.

Notes:

**Jobsite will be left clean once completed.

**Utility locates are called in before any digging; work starts about a week after acceptance.

**The sidewalk crossing is hand dug under the walk - no concrete cutting.

Warranty:

**12 months workmanship on the drainage system.



Payment Terms:

Total Project Cost: \$3,195.00

10% Customer Discount: -\$319.50

5% Repeat Customer Discount: -\$159.76

Total Project Cost: \$2,715.74

Deposit to Schedule: \$1,357.87

Final Payment: \$1,357.87

Check is a preferred method.

**You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

Cards not eligible for payment:

- Virtual Affirm credit card

Validity: valid until September 25, 2026.



buried corrugated pipe - six downspouts into one discharge line - 321 Janes Way, Chesapeake, VA 23320